

## Port of Morrow Waste Water Treatment Facility Boardman, Oregon



|                    |   |
|--------------------|---|
| <b>DESCRIPTION</b> | <p>Construction management of \$900,000 wastewater treatment, containment, and pumping facility which includes a Raw Waste Sump and Effluent Building to support a new Cheese Making Facility currently under construction within the Port of Morrow development park.</p> <p>System capacity designed at 1.5 MGD Two cast-in-place concrete containment/pump buildings installed using six (6) De-watering wells. Piping from 8"-36 " installed at depths up to 12' in sandy soils..</p> |
| <b>SERVICES</b>    | Construction Management/Prime Consultant  |
| <b>BUDGET</b>      | \$1 Million   |
| <b>FINAL COST</b>  | \$1 Million   |
| <b>CONTACT</b>     | Gary Neal<br>General Manager<br>Port of Morrow<br>(541) 481-7678<br>PO Box 200<br>Boardman, Oregon  |